

## **All Pre-Owned Equipment is Thoroughly Tested Prior to Sale**

### ***CLEAN***

Outside unit is totally cleaned including hoses, tubes, clamps and all adapters. Inside unit totally cleaned - including removing the unit's back and applicable filter!

### ***INVENTORY***

ALL adapters\* are inventoried and I purchase any missing adapters to complete the adapter kit. All adapters are outfitted with their associated clips, retainers and O-rings. \*Applies to machines that include adapters.

### ***DIAGNOSTICS***

Perform a complete control panel PCB diagnostic consisting of applying power and checking for proper software operation. Ensure control panel passes memory test and lighting sequence. Confirm all LEDs operational, reverse polarity and solenoid functions properly working.

### ***PRESSURE RELIEF VALVE CALIBRATION***

Ensure pump is operating at correct pressure. Adjust applicable relief valves as needed to meet MOTORVAC® specifications.

### ***REPAIRS***

Correct any internal leaks and replace all defective internal fittings with new fittings. Units are drained, the inside of the unit's fluid tank cleaned and a new filter is installed.